



**US Army Corps
of Engineers**
Seattle District



WASHINGTON STATE
DEPARTMENT OF
E C O L O G Y

Joint Public Notice Of In-lieu Fee Program Addendum

US Army Corps of Engineers

Regulatory Branch
Post Office Box 3755
Seattle, Washington 98124-3755
Telephone (206) 764-6903
Email: gail.m.terzi@usace.army.mil
Attention: Ms. Gail Terzi

WA Department of Ecology

Shorelands and Environmental
Assistance Program
Post Office Box 47600
Lacey, Washington 98504-7600
Telephone: (360) 407-6861
Email: bmur461@ecy.wa.gov
Attention: Mr. Brad Murphy

Public Notice Date: November 18, 2013

Expiration Date: December 18, 2013

Reference No.: NWS-2009-495

**Name: King County Mitigation
Reserves Program In Lieu Fee**

Interested parties are hereby notified that the U.S. Army Corps of Engineers (Corps) and the Washington State Department of Ecology (Ecology) are soliciting comments and information necessary to evaluate any impacts on the public interest from the proposed inclusion of a portion of the McElhoe-Pearson Restoration Project (Mitigation Plan) as a restoration site that has been selected for funding through King County's In Lieu Fee (ILF) Program. The sponsor for the program is King County. The King County ILF Program Instrument was authorized on March 12, 2012.

King County is proposing to modify their ILF Program Instrument by adding the Mitigation Plan to the Program Instrument, also known as the King County Mitigation Reserves Program (MRP). The Mitigation Plan has been developed in accordance with 33 CFR Parts 325 and 332.2 and describes project elements, performance measures, and maintenance and monitoring plans for implementation and long-term management of the McElhoe-Pearson Restoration project on the Snoqualmie River (See enclosed color drawings).

WATERWAY AND LOCATION OF PROPOSED PROJECT: The proposed ILF Mitigation Project site is located on approximately two acres adjacent to the Snoqualmie River near RM 23, in WRIA 7, north of the City of Carnation in unincorporated King County.

PROPOSED WORK AND PURPOSE: The ILF Mitigation Project referred to as the McElhoe-Pearson Restoration Project (Mitigation Project) is for impacts associated with a Washington State Department of Transportation (WSDOT) Project on Tokul Creek. The Mitigation Project will create additional rearing and refuge habitat for salmonid species in the Snoqualmie River. Major project elements include:

- Creation of new side channel
- Breaching a levee to create a connection from side channel to existing riverine wetlands
- Wetland restoration and enhancement

The ecological goals of the project include:

- Restore rearing and refuge habitat
- Restore the connection between channel and floodplain
- Maximize habitat value while protecting private property and public infrastructure
- Reduce flood hazards and flood facility maintenance

The total restoration of the area attributable to the mitigation for the WSDOT impact at Tokul Creek includes:

- New connection to Snoqualmie River (at OHWM) of 41,426sf (0.95ac) of previously disconnected wetland area, resulting from the excavation of a new side channel and breach of a levee
- Excavation and grading of 9,191sf (0.21ac) of side channel and levee breach to connect existing backwater channel to previously disconnected wetland area.
- Enhancement of 16,960sf (0.39ac) of existing wetland and riparian areas. Actions include weed control and native planting.
- Installation of nine (9) large wood root wad structures along the backwater channel near the mouth of the backwater.

Tokul Creek Impacts for which mitigation is being implemented:

Table 1. Summary of Tokul Creek Project Stream and Buffer Impacts

King County classification	Permanent Impacts (ft ² /Acre)		Temporary Impacts (ft ² /Acre)	
	Stream	Buffer	Stream	Buffer
Shoreline	15,580/0.36	7,344/0.17	7,269/0.17	8,396/0.19

A draft Mitigation plan is available upon request from:

Michael Murphy, Mitigation Reserves Program Manager
 King County Department of Natural Resources and Parks
Michael.murphy@kingcounty.gov
 206-477-4781

BACKGROUND: King County (KC) and WSDOT reached an agreement to use KC's ILF Program, to meet an outstanding WSDOT mitigation need related to 2010 emergency repairs of a State Route 202 bridge resulting in impacts to Tokul Creek (Corps Reference NWS-2010-800), a tributary to the Snoqualmie River in Watershed Resource Inventory Area 7.

The regulatory agencies requiring compensatory mitigation for the emergency action for the WSDOT repair project are the Washington Department of Fish and Wildlife (WDFW) and the King County Department of Permitting and Environmental Review (KCDPER). Both WDFW and KCDPER agreed to WSDOT's use of the ILF. The Tokul Creek project and associated permanent and temporary impacts is not subject to this public notice.

KC has designated the McElhoe-Pearson restoration site on the Snoqualmie River as the Mitigation Site that will meet the WSDOT mitigation obligation. By paying a mitigation fee, WSDOT irrevocably transferred to KC all obligations related to implementation, maintenance, monitoring, reporting, etc. of the McElhoe-Pearson Restoration Project. KC implemented the McElhoe-Pearson Restoration Project in the fall of 2012, and completed planting in February 2013. KC will monitor and maintain the mitigation project according to the terms of the Mitigation Plan, which will be appended to the ILF Program Instrument. The Corps issued Nationwide Permit's (NWP) 3 and 27 for construction of the Mitigation Project on June 22, 2012 (Corps Reference NWS-2012-201). Ecology issued an individual 401 water quality certification on June 28, 2012.

The mitigation project is located at a site that received Salmon Recovery Funds but the funds received from the grant were not sufficient to complete the project. With WSDOT purchasing credits from the King County ILF Program, in combination with the Salmon Recovery Funds, King County is able to implement the entire project. The King County ILF Program Instrument contains the following language that addresses this situation (Appendix D, Section 3.6):

"Mitigation credit shall not be available from other County, State or Federal restoration projects in existence outside the MRP. In cases where mitigation sites are adjacent to or near to existing or proposed restoration sites, the Mitigation Plan (see Appendix K) will clearly show areas of restoration (where no credit is available) and where mitigation credit can be generated.

The MRP will not derive credit from any project(s) already funded with Salmon Recovery Fund money or any projects already planned and funded or completed to meet a permit condition.

However, there may be cases when MRP mitigation fees can be used to implement a salmon recovery project or other restoration project. For this to occur, all of the following must apply:

- The project is not funded;
- There is not a restriction related to the funding used to acquire a site where the project will occur; and
- The project is not a requirement associated with a permit (e.g., a mitigation project).

The federal rule, [332.3(j)(2)] states:

Except for projects undertaken by federal agencies, or where federal funding is specifically authorized to provide compensatory mitigation, federally-funded aquatic resource restoration or conservation projects undertaken for purposes other than compensatory mitigation, such as the Wetlands Reserve Program, Conservation Reserve Program, and Partners for Wildlife Program activities, cannot be used for the purpose of generating compensatory mitigation credits for activities authorized by DA permits. However, compensatory mitigation credits may be generated by activities undertaken in conjunction with, but supplemental to, such programs in order to maximize the overall ecological benefits of the restoration or conservation project.

If mitigation fees are used to implement projects or portions of projects prioritized in a Salmon Recovery Plan, the impacts for which mitigation fees were collected must be accounted for when measuring progress toward watershed-wide salmon recovery goals. For each mitigation project implemented through the MRP, the MRP Manager will provide details of the mitigation project to WRIA Forum staff for entry into the Habitat Work Schedule, which is an online mapping and tracking tool used to measure progress and increase accountability for implementation of salmon recovery projects statewide. At minimum, information added to the Habitat Work Schedule database will include the amount of funding from mitigation fees, the type and amount of enhancement, restoration, creation, etc. to aquatic resources and buffers at the mitigation project, and the reports about permitted impact projects from which mitigation fees were derived (see Appendix G, Section 6.1). Mitigation projects will be clearly categorized as such in the Habitat Work Schedule database so it is evident to salmon recovery planning staff that ecological lift at mitigation projects is achieved at the expense of allowing permitted ecological impacts elsewhere in the watershed.”

AUTHORITY; Issuance of a Public Notice regarding proposed ILF receiving sites is required pursuant to: “Compensatory Mitigation for Losses of Aquatic Resources; Final Rule,” as published in the April 10, 2008, Federal Register, Vol. 73, No. 70, Pages 19594-19705 (33 CFR Parts 325 and 332).

EVALUATION OF PROPOSAL: The Corps and Ecology are soliciting comments from the public; Federal, State, and local agencies and officials; Indian Tribes; and other interested parties in order to consider and evaluate this proposed ILF receiving site. The Corps and Ecology, in evaluating this proposal, will consider any comments received.

This is not an application for work in waters of the United States. The Corps issued NWP’s 3 and 27 for construction of the project on June 22, 2012. Ecology issued an individual 401 water quality certification on June 28, 2012. After preliminary approval from the KC ILF Program Interagency Review Team, KC has constructed the project at the risk of subsequently receiving comments on the mitigation plan design or credit, which may necessitate resolution. During processing of NWPs 3 and 27, the proposed work was reviewed under the Endangered Species Act of 1973, the Magnuson-Stevens Fishery Conservation and Management Act, as amended by the Sustainable Fisheries Act of 1996 and the National Historic Preservation Act. The project is in compliance with these laws and no further action is required.

COMMENT AND REVIEW PERIOD – Conventional mail or e-mail comments on this proposed ILF receiving site will be accepted and made part of the record and will be considered in determining whether it would be in the public interest to authorize this addendum to the KC ILF Program Instrument. In order to be accepted, e-mail comments must originate from the author’s e-mail account and must include on the subject line of the e-mail message the ILF sponsor’s name and reference number as shown below. All e-mail comments should be sent to gail.m.terzi@usace.army.mil at the Corps and bmur461@ecy.wa.gov at Ecology.

Conventional mail comments should be sent to the U.S. Army Corps of Engineers, Regulatory Branch, Attention: Ms. Gail Terzi, Post Office Box 3755, Seattle, Washington 98124-3755 and/or to the Department of Ecology, Attention: Mr. Brad Murphy, Post Office Box 47600, Olympia, Washington 98504-7600.

Any person may request, in writing, within the comment period, that a public hearing be held to consider the Mitigation Plan. Requests for public hearings shall state, with particularity, the reasons for holding a public hearing.


Either conventional mail or e-mail comments must include the sponsor's name and reference number, as shown below, and the commenter's name, address, and phone number. All comments received will become part of the administrative record and are subject to public release under the Freedom of Information Act, including any personally identifiable information such as name, phone numbers, and addresses. All comments, whether conventional mail or e-mail must reach this office, no later than the expiration date of this public notice to ensure consideration. Please include the following name and reference number with any comments:

King County Mitigation Reserves Program ILF (McElhoe-Pearson ILF Mitigation Site)
NWS-2009-495

ENCLOSURES Drawings (13)

McElhoe-Pearson Mitigation Project

PRE-PROJECT CONDITIONS



This graphic shows the pre-project conditions at the McElhoe-Pearson restoration project on the Snoqualmie River. The project involves excavating a backwater side channel and breaching a levee to reconnect riverine approximately one acre of wetlands to the river, including a number of habitat features to improve wetland functions.

The elements of the project meeting the WSDOT mitigation need are shown on the subsequent page.

Legend

- Levee Maintained by King County
- Cross Levee
- Existing Wetland Boundaries
- Parcel boundaries




0 100 200 300 Feet



Latitude: 47.6616
Longitude: -121.92673

McElhoe-Pearson Restoration Project: Mitigation Project Elements

POST-PROJECT CONDITIONS



This graphic shows the project elements implemented at the McElhoe-Pearson mitigation project on the Snoqualmie River. The project involves excavating a backwater side channel and breaching a levee to reconnect approximately two acres of riverine wetlands to the river, including a number of habitat features to improve wetland functions.

The elements of the project meeting the WSDOT mitigation need are shown on the graphic to the left and summarized in the table below.

Legend

	WSDOT Mitigation Area		Existing Wetland Boundaries
	Levee Maintained by King County		Riparian/Wetland Planting Area
	Cross Levee		Large Wood Features (9 pcs)
	Levee Breach Area		


Impact Amounts (All Offsite at Tokul Cr):

Aquatic Resource Type	Permanent Impacts	Replacement Ratio	Mitigation Requirement (sf)
Stream	15,580	1.25:1	19,475
Riparian	10,986	1.5:1	11,016
LWD	~12 trees	0.67:1	9 key pieces

Mitigation Amounts:

Mitigation Project Elements	Area (sf)
Existing wetland area enhanced by new connection	41,426
Excavation of side channel	9,191
Riparian planting (side channel & around LWD)*	16,960
Installation of LWD	9 key pieces

*Includes riparian areas along side channel and around log clusters




Purpose: McElhoe-Pearson ILF Mitigation Project
Project Sponsor: King County DNRP
Date: November 7, 2013

NWS-2009-495

Location: 65XX 310th Ave NE
Sec/Twp/Rng: 09/26N/07E
County: King State: WA


VICINITY MAP
N15



INDEX

SHEET	DESCRIPTION
G1	COVER, VICINITY MAP & INDEX
G2	LEGEND & ABBREVIATIONS
G3	EXISTING SITE PLAN
G4	PROPOSED SITE PLAN
G5	OUTLET CHANNEL, PROFILES & SECTIONS
G6	WEIR AND ROAD EMBANKMENT DETAILS
G7	LOG CLUSTER DETAILS
G8	TESS PLAN
G9	TESS DETAILS
G10	PLANNING PLAN

FIELD BOOK	D. MATOS	5/2011	APPROVER: JIMMIE CUMMINGS	DATE: 5/2012	FED. AID No.	PROJECT No.	1034170				King County Department of Natural Resources and Parks Water and Regional Resources Division Rural and Regional Resources Section Ecological Restoration and Engineering Unit Christie True, Director	McELHOE PEARSON RESTORATION PROJECT 2012 COVER, VICINITY MAP & INDEX NWS-2009-495	SHEET G1 OF 11 SHEETS 2006-40
DESIGNED BY	R. CLARK	5/2011	PROJECT MANAGER: ELMAR TORRES	DATE: 5/2012	PROJECT No.	11029							
CHECKED BY	T. ORV	5/2011	DESIGNED BY: CAROLYN BERTRAM, P.E.	DATE: 5/2012	SURVEY No.								
			DESIGNED BY: KAY REYNOLDS	DATE: 5/2012	MAINTENANCE DIVISION No.	2							



King County
 Department of Natural Resources and Parks
 Water and Land Resources Division
 Rural and Regional Resources Section
 Ecological Restoration and Engineering Unit

Christie True, Director
 Department of Natural Resources and Parks

McELHOE PEARSON
RESTORATION PROJECT 2012

CALL 2 WORKING DAYS
 BEFORE YOU DIG
 1-800-424-5555

UNDESIGNATED UTILITY LOCATIONS (SEE APPROX.)

GENERAL NOTES:

- HORIZONTAL DATUM: WASHINGTON STATE PLAN COORDINATE SYSTEM, NORTH ZONE (NAD 83/97).
- VERTICAL DATUM: NAD 88
- KING COUNTY WILL STAKE CONTROL, ROW, AND VEGETATION TO BE PROTECTED.
- BEFORE BEGINNING CONSTRUCTION THE CONTRACTOR SHALL VERIFY THAT EXISTING CONDITIONS ARE AS INDICATED IN THE PLANS AND SPECIFICATIONS.
- RESTORATION PLANNING WILL BE COMPLETED BY THE OTHER FOLLOWING CONTRACTOR PROJECT COMPLETION.
- ALL LOCATIONS OF EXISTING UTILITIES SHOWN HEREON HAVE BEEN ESTABLISHED BY FIELD SURVEY OR OBTAINED FROM AVAILABLE RECORDS AND SHOULD THEREFORE BE CONSIDERED ACCURATE. THE CONTRACTOR SHALL VERIFY THE ACCURACY OF ALL UTILITY LOCATIONS SHOWN AND TO FURTHER DISCOVER AND AVOID ANY OTHER UTILITIES NOT SHOWN HEREON WHICH MAY BE AFFECTED BY THE IMPLEMENTATION OF THIS PLAN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE IDENTIFICATION OF ALL UTILITIES. UNDERGROUND UTILITIES LOCATION SERVICE (1-800-424-5555) AT LEAST 48 HOURS PRIOR TO CONSTRUCTION. THE ENGINEER SHALL BE CONTACTED IMMEDIATELY IF A CONFLICT EXISTS.

CONSTRUCTION SEQUENCE:


SITE PREPARATION:

- CONDUCT A PRE-CONSTRUCTION MEETING.
- INSTALL TEMPORARY ACCESS AS SHOWN ON PLANS.
- INSTALL COMPOST SOCKS AS SHOWN ON PLANS.
- MAINTAIN TEST MEASURES IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS AND GENERAL IN-WATER FEATURES.

DESIGN FEATURES:

- CONSTRUCT ROAD STABILIZATION AND SHOULDER BERM.
- INSTALL TURBIDITY CURTAINS AS SHOWN ON PLANS.
- BREACH LEVEE AND EXCAVATE OUTLET CHANNEL AND AS SHOWN ON PLANS. STAGE ALL SLASH AND FELLED TREES FOR RE-USE ON-SITE.
- PLACE SLASH AND FELLED TREES AS FIELD DIRECTED.
- DEPOSIT SPOILS ON SITE AS SHOWN ON PLANS AND FIELD DIRECTED.
- FINAL GRADE WETLAND RESTORATION AND PLACE SLASH AND FELLED TREES AS FIELD DIRECTED.
- EXCAVATE KING COUNTY ACCESS ROAD, INSTALL CULVERT, AND BACKFILL ACCESS ROAD AS SHOWN ON PLANS.
- FINAL GRADE WETLAND EXCAVATION AREA AND INSTALL SLASH AND FELLED TREES PER FIELD DIRECTION.
- INSTALL LOG CLUSTERS.


DRAWING REFERENCE:



ABBREVIATIONS:

- INDICATES THAT THE DETAIL/SECTION IS SHOWN ON THE SAME DRAWING
- INDICATES THAT THE DETAIL/SECTION IS UNUSUALLY TYPICAL THROUGHOUT PROJECT EXCEPT WHERE OTHERWISE NOTED
- SPECIES THAT DETAIL/SECTION WAS TAKEN FROM SEVERAL DRAWINGS
- NOT TO SCALE
- TEMPORARY EROSION & SEDIMENT CONTROL
- WATER SURFACE ELEVATION

LEGEND:



FIELD BOOK	D. MILES	8/2011	APPROVED, DATE CONSTRUCTION	8/2012	FED. AID No.	-
EXAMINED	R. OLIVER	5/2011	PROJECT MANAGER	FLORA KOPF	PROJECT No.	1054170
DRAWN	T. GRAY	5/2011	DESIGNER	CHAROLYN BURCHARDT, P.E.	SURVEY No.	11029
CHECKED	T. GRAY	5/2011	DESIGN CHECKER	KAY KOTAMURA	MAINTENANCE No.	2
DATE	8/2012					



King County
 Department of Natural Resources and Parks
 Wetland and Riparian Services Section
 Ecological Restoration and Engineering Services Unit
 Chief, Trip Director


McHoe Pearson
 RESTORATION PROJECT 2012
 LEGEND & ABBREVIATIONS
 NWS-2009-495

SHEET
 02
 OF
 11
 SHEETS
 2006-40

CALL 2 WORKING DAYS
 BEFORE YOU DIG
 1-800-424-5555

Page 4 of 13

FIELD BOOK	D. MALLOS	5/2011	APPROVED DATE CONSTRUCTION	6/2012	FED. AID NO.	
DRAWN BY	R. CLARK	8/2011	PROJECT	PAULA NOPP	1034170	
CHECKED BY	T. GRAY	5/2011	DESIGNER	CAROLYN BIRCHMANT, P.E.	11028	
DESIGNER			DESIGN ENGINEER	KAY KOTAMURA	6/2012	
DATE			PROJECT SURVEY NO.	11028		
			MAINTENANCE DIVISION NO.	2		



PT#	NORTHING	EASTING	ELEV.
100	242507.88	1371822.84	82.71
101	242521.49	1371838.78	81.48
102	242500.57	1371834.78	85.18
104	242883.24	1371111.85	85.18
105	243028.43	1371130.87	85.30
106	242888.33	1371211.17	85.88

MCELROY PEARSON RESTORATION PROJECT 2012
 EXISTING SITE PLAN
 NWS-2009-405




CALL 2 WORKING DAYS BEFORE YOU DIG
 1-800-424-5555
 (UNDESIGNED UTILITY LOCATIONS ARE APPROX.)

Page 5 of 13

SHEET C1 OF 11 SHEETS
 2006-40

GENERAL CONSTRUCTION NOTES:

1. ACTUAL EXCAVATION LIMITS FOR OUTLET CHANNEL AND DESIGNATED WETLAND AREAS TO BE FIELD DIRECTED TO MINIMIZE CLEANING OF VEGETATION.
2. SCRAPE SAND FROM OUTLET CHANNEL AND PLACE ON TOP OF LEVEE AT 6-INCHES THICK FOR PLANNING SOIL ADJUSTMENT.
3. FIELDED TREES DURING CONSTRUCTION WITH MIN. DIAMETER OF 6-INCHES TO BE FIELDED DURING CONSTRUCTION. FIELDED TREES TO BE UP AGAINST THE SOUTH SIDE (UPSTREAM SIDE) OF A MINIMUM OF 2 LIVE VERTICAL TREES. FIELDED TREES ALONG OUTLET CHANNEL WILL BE TRIPPED SUCH THAT ROOTWAYS ARE FACING NEW CHANNEL.
4. FIELDED TREES SMALLER THAN 6-INCH DIAMETER AND LESS THAN 20-FEET LONG CAN BE SPREAD ON-SITE ON POINT BAR, LOG CLUSTERS, AND WETLAND AREA AS FIELD DIRECTED.
5. SPOILS 1 APPROXIMATELY 20' LONG BY 30' WIDE. GREAT SPOILS 1 WITH TOP SOILS OF FIELDED TREES ON BOTTOM AND OUTLET CHANNEL GRADE SPOILS AT 34-IV SS ON WEST SIDE AND FLUSHED WITH EXISTING GRADE AT ELEVATION 59' ON EAST SIDE.



FIELD BOOK:	D. MALLOS	5/2011
SKETCH:	R. CLARK	5/2011
DESIGN DATE MAP:	T. GRAY	5/2011
CHECKED:		
APPROVED, CIVIL ENGINEER:	DAVID CONNOR	8/2/2012
PROJECT:	FAUNA NHP	8/2/2012
DESIGNER:	CHRISTOPHER BUTCHART, P.E.	8/2/2012
DESIGN PARTNER:	KAY KEMURA	8/2/2012
FED. AID NO.:		
PROJECT NO.:	1034170	
SURVEY NO.:	11029	
MANAGEMENT DIVISION NO.:	2	







King County
 Department of Natural Resources and Parks
 Water and Land Resources Division
 Road and Regional Services Section
 and Engineering Services Unit
 Charles Tinn, Director

ME SHOE PEARSON RESTORATION PROJECT 2012
 PROPOSED SITE PLAN
 NWS-2009-495

SHEET **C2**
 OF **11**
 SHEETS
2006-40

CALL 2 WORKING DAYS BEFORE YOU DIG
 1-800-424-5555
 (UNDERGROUND UTILITY LOCATIONS ARE APPROX.)



- NOTES:**
1. OUTLET CHANNEL TO BE EXCAVATED AT CONSISTENT GRADE FROM BEGINNING AND END STATIONS SHOWN ON THE PLANS. SPOILS TO BE PLACED PER DETAIL D.
 2. TOPICAL OUTLET CHANNEL TO BE 5' WIDE AT BOTTOM AND EXCAVATED AT 2H:1V UNTIL LAST 2 FEET BEFORE TYPING INTO EXISTING GRADE AT 1H:1V. SIDE SLOPES MAY VARY AS FIELD DIRECTED TO MINIMIZE VEGETATION DISTURBANCE.
 3. BENCHES AT ELEV. 55' THROUGH LARGEST BREACH TO BE FIELD DIRECTED AS LOW FLOW CHANNEL. ALIGNMENT VARIES.
 4. TOE ROCK WITHIN EXISTING LEVEE PRISM TO BE 5' THICK OF HEAVY LOOSE RIPRAP FROM ELEV. 50' TO 55'.
 5. 8" DIA. OR GREATER AND 20' OR SHORTER FELLED TREES DURING CONSTRUCTION TO BE PLACED ON SOUTH SIDE AGAINST A MINIMUM OF TWO STANDING TREES OF MIN. 4" DIA.





FIELD BOOK:	D. MALTON	5/2/2011	APPROVED:	DAVE CONNORSON	8/2/2012	FEA. AND No.	
SURVEY:	R. CLARK	5/2/2011	PROJECT:	EVANNA HOPP	8/2/2012	PROJECT No.	1034170
STAKE DATE:	T. ORAY	5/2/2011	DESIGNED:	OROLYN BUDGART, P.E.	8/2/2012	SPRINT No.	11029
CHECKED:			DESIGN ENGINEER:	KW. KITAMURA	8/2/2012	MAINTENANCE DIVISION No.	2
REVISION:							



McELHO PEARSON RESTORATION PROJECT 2012
OUTLET CHANNEL PROFILES & SECTIONS
 NWS-2009-495
 SHEET C3 OF 11
 SHEETS 2006-40

CALL 2 WORKING DAYS BEFORE YOU DIG
 1-800-424-5555

Page 7 of 13




SHOULDER BERM NOTES:

1. ROADSIDE TOE OF BERM TO BE OFFSET 4' FROM EDGE OF PAVEMENT TO PROVIDE SHOULDER.
2. SHOULDER TO MATCH EXISTING PITCH OF PAVEMENT WITH A MINIMUM OF 24" OF LIGHT LOOSE RIPRAP.
3. THE SHOULDER INTO EXISTING PAVEMENT WITH CARE NOT TO DISTURB THICKENED AND EXTENDED PAVEMENT EDGES. THE PAVEMENT AND TAKE CARE NOT TO DISTURB.
4. FILL VOIDS IN SHOULDER WITH 4' MINUS QUARRY SPALLS AND 1-1/4" CRUSHED ROCK.
5. INFILTRATION TRENCH ALONG CORNER ROAD SECTION BETWEEN STATIONS 13+75 TO 14+88 TO BE OFFSET 2' FROM EDGE OF PAVEMENT WITH MINIMUM DIMENSIONS OF 2' WIDE BY 3' DEEP. BACKFILL WITH LIGHT LOOSE RIPRAP.
6. BERM CORE TO BE BUILT IN 8" LIFTS AND COMPACTED W/ ROLLER TO 95% MAX. DENSITY AS DETERMINED BY MODIFIED PROCTOR.
7. DENSITY TEST OF BERM CORE TO BE TAKEN BEFORE COVERED W/ LIRR.
8. POUR SILTY SAND MIX BERM CORE FIRST, THEN OVERLAY W/ LIRR.


CALL 2 WORKING DAYS BEFORE YOU DIG
1-800-424-5555
(DRAINAGE UTILITY LOCATIONS ARE APPROX.)

FIELD BOOK:	D. MALLOS	5/2/2011
SURVEYOR:	R. CLARK	5/2/2011
START DATE:	F. CHAY	5/2/2011
CHECKED:		
DATE:		
APPROVED:	DAVE COMPTON	9/2/2012
PROJECT:	FLANK RIPP	1034170
DESIGNER:	CAROLYN BURCHETT, P.E.	11028
DRAWN BY:	KAY TERPILSKA	9/2/2012
DATE:		
DESIGN CENTER:		
KEY:		
MAINTENANCE DIVISION NO.:	2	




McELHO PEARSON RESTORATION PROJECT 2012
ROAD STABILIZATION DETAILS
NWS-2009-495
SHEET 05 OF 11 SHEETS
2006-40

Page 9 of 13




LOG CLUSTER DETAIL - PLAN (TYP)
SCALE N.T.S.




LOG CLUSTER DETAIL - SECTION (TYP)
SCALE 1"=5' HORIZ, 1"=2.5' VERT.

- WOOD ENHANCEMENT NOTES:**
1. ALL LOGS TO BE DOUGLAS FIR OR CEDAR. LOGS WITH ROOTWADS TO BE A MINIMUM OF 2' DIA.
 2. LAYER 1 LOG TO BE SEMI-PARALLEL TO FLOW WITH ROOTWAD FACING UPSTREAM.
 3. ANCHOR LAYER 1 LOG WITH 4-MAN HOLE ROCKS AS SHOWN ON THE PLAN AND PER DETAIL ON THIS SHEET.
 4. LAYER 2 LOGS TO BE PERPENDICULAR TO FLOW EMBEDDED A MINIMUM OF 20" INTO THE BANK.
 5. ANCHOR LAYER 2 LOGS WITH 4-MAN HOLE ROCKS ON EACH SIDE OF LOG.
 6. SLASH TO BE PLACED UNDER EACH LOG BEFORE PLACEMENT.



ROCK ANCHOR FOR LOGS
SCALE N.T.S.

FIELD BOOK	D. MALINS 02/2011	APPROVED DATE CONSTRUCTION	9/2012	FED. AID No.	-
SURVEY	R. CLARK 5/2011	PROJECT MANAGER	9/2012	PROJECT No.	1034170
DESIGNED	T. CRAY 5/2011	DRAWN	9/2012	SURVEY No.	11028
CHECKED		DESIGN PARTNER	9/2012	MAINTENANCE DIVISION No.	2
DATE		BY			
REVISION					




King County
Department of Natural Resources and Parks
Wildlife and Land Resources Division
Ecological Restoration and Engineering Services Unit
Cristina Tava, Director

McELHOO PEARSON
RESTORATION PROJECT 2012
LOG CLUSTER DETAILS
NWS-2009-495

SHEET
06
OF
11
SHEETS
2006-40


CALL 2 WORKING DAYS BEFORE YOU DIG
1-800-424-5555
(UNDERGROUND UTILITY LOCATIONS ARE APPROX.)



- NOTES:**
1. ALL MATERIALS SPILLED, DROPPED, WASHED OR TRACKED FROM VEHICLES ONTO ROADWAYS MUST BE REMOVED IMMEDIATELY.
 2. VEHICLE TIRES SHALL BE INSPECTED TO ENSURE THEY ARE FREE OF MUD BEFORE ENTERING PUBLIC ROADWAYS.
 3. PROVIDE FLAGGING FOR CONSTRUCTION VEHICLES ENTERING AND LEAVING SITE AND ENTERING PUBLIC ROADWAYS.
 4. CONTRACTOR SHALL MAINTAIN AND ADJUST EXISTING STABILIZED CONSTRUCTION ENTRANCES AS NEEDED TO CONTROL SEDIMENT.

STABILIZED TEMPORARY CONSTRUCTION ACCESS


NIS A



- NOTE:**
1. COMPOST SOCK SHALL BE 100% NATURAL AND BIODEGRADABLE MATERIAL AND INSTALLATION SHALL BE PER B-01.3(12) AND B-14.5 (b).


COMPOST SOCK

NIS B



WEIGHTED SILT FENCE (TYP.)

NIS C



48" LCPPE CULVERT DETAIL

NOTE:

1. GRAVEL BACKFILL FOR PIPE ZONE BEDDING SHALL CONSIST OF GRANULAR BEDDING OR GRANULAR SAND EQUIVALENT MATERIAL PER THE FOLLOWING GRADATION:

GRAVEL BACKFILL FOR PIPE ZONE BEDDING	PERCENT PASSING
NO. 40	99-100
NO. 200	75-100
NO. 4	50-100
NO. 20	20-80
NO. 40	3-24
NO. 200	1.0-100
SAND EQUIVALENT	35 MIN.

FIELD BOOK:	D. MATOS	5/2011
STATIONER:	R. CLARK	5/2011
DESIGNED:	T. ORW	5/2011
APPROVED:	DAVE CHANDRAN	8/2012
PROJECT:	FAUNA NOPP	8/2012
DESIGNED:	CHANDRAN ARCHITECT, P.C.	8/2012
DESIGNED:	KM KRAMER	8/2012
DESIGNED:	MANITOWOC DIVISION	2

King County
Department of Public Utilities and Public Works
Water and Land Resources Division
Water and Land Resources Section
and Engineering Services Unit
Chelsie Tom, Director

McElho Pearson Restoration Project 2012
TESC DETAILS
NYS-2009-495

CALL 2 WORKING DAYS BEFORE YOU DIG
1-800-424-5555
(underground utility locations are shown)

SHEET **C8** OF **11** SHEETS
2006-40

Page 12 of 13

