
SITE PLAN



<u>SHEET</u>	DESCRIPTION
1	VICINITY MAP AND SHEET INDEX
2	LEGEND AND NOTES
3	GRADING PLAN AND NOTES
4	GRADING AND EROSION CONTROL NOTES
5	EROSION AND SEDIMENT CONTROL PLAN
6	CROSS SECTIONS
7	PLANTING PLAN, DETAIL AND NOTES
8	SOIL TEST PIT LOCATIONS

PROJECT DESCRIPTION:
NORTH WIND'S WEIR INTERTIDAL RESTORATION
VICINITY MAP AND INDEX SHEET

ADDRESS LINE 1:

DUWAMISH INTERTIDAL NEAR 2724 S. 112th ST.

CITY, COUNTY, STATE, ZIP CODE TUKWILA, KING, WA, 98168 APPLICANT: USACE—Se

USACE—Seattle District King County DNRP


REFERENCE No.: PL-04-02

WATERWAY: DUWAMISH RIVER

S.T.R.: SE 1/4 S.4, T.23N, R.4E

No. 1 Of 8 Sheets

NOT TO SCALE



PROJECT DESCRIPTION: NORTH WIND'S WEIR INTERTIDAL RESTORATION LEGEND AND NOTES

ADDRESS LINE 1: DUWAMISH INTERTIDAL NEAR 2724 S. 112TH ST.

CITY, COUNTY, STATE, ZIP CODE TUKWILA, KING, WA, 98168 APPLICANT:

USACE—Seattle District King County DNRP


REFERENCE No.: PL-04-02

WATERWAY: DUWAMISH RIVER

NO SCALE

S.T.R.: SE 1/4 S.4, T.23N, R.4E

No. 2 Of 8 Sheets



TEMPORARY EROSION AND SEDIMENTATION CONTROL (TESC) NOTES

- The implementation of these TESC plans and the construction, maintenance, replacement, and upgrading of these TESC facilities is the responsibility of the TESC supervisor until all construction is approved.
- 2. The boundaries of the clearing limits shown on this plan shall be clearly identified by a continuous length of survey tape (or fencing, if required) prior to construction. During the construction period, no disturbance beyond the clearing limits shall be permitted. The clearing limits shall be maintained by the TESC supervisor for the duration of construction.
- The TESC facilities shown on this plan must be constructed prior to or in conjunction with all clearing and grading so as to ensure that the transport of sediment to surface waters, drainage systems, and adjacent properties is minimized.
- 4. The TESC facilities shown on this plan are the minimum requirements for anticipated site conditions. During the construction period, these TESC facilities shall be upgraded as needed for unexpected storm events and modified to account for changing site conditions (e.g. additional sump pumps, relocation of ditches and silt fences, etc.)
- 5. The TESC facilities shall be inspected daily by the TESC supervisor and maintained to ensure continued proper functioning. Written records shall be kept of weekly reviews of TESC facilities during wet season (Oct. 1 to March 31) and monthly reviews during the dry season (April 1 to Sept. 30)
- Any areas of exposed soils, including roadway embankments, that will not be disturbed for two days during the wet season or seven days during the dry season shall be immediately stabilized with the approved TESC methods 7. (e.g., seeding, mulching, plastic covering, etc.).
- Any area needing TESC measures, not requiring immediate attention, shall be addressed within fifteen (15) days.
- 8. The TESC facilities on inactive sites shall be inspected and maintained a minimum of once a month or 48 hours following a storm event.
- The clearing operation shall not flush sediment-laden water into the downstream system.
- 10. Stabilized construction entrances and roads shall be installed at the beginning of construction and maintained for the duration of the project. Additional measures, such as wash pads may be required to ensure that all paved areas are kept clean for the duration of the project.
- 11. Where straw mulch for temporary erosion control is required, it shall be applied at a minimum thickness.

TESC CONSTRUCTION SEQUENCE

- Pre-construction
- Flag or fence clearing limits.

 Post sign with name and phone number of TESC supervisor.

 Grade and install construction entrance(s).
- Install perimeter protection (silt fence, brush barrier, etc.).

- Construct sediment ponds and traps.
 Grade and stabilize construction roads.
 Construct surface water controls (interceptor dikes, pipe slope drains, etc.) simultaneously with clearing and grading for project development.

- simultaneously with clearing and grading for project development.

 Maintain erosion control measures in accordance with King County standards and manufacturer's recommendations.

 Relocate erosion control measurers or install new measures so that as site conditions change the erosion and sediment control is always in accordance with the King County TESC minimum requirements.

 Cover all areas that will be unworked for more than seven days during the dry season or two days during the wet season with straw, wood fiber mulch, compost, plastic sheeting or equivalent.

- Stabilize all areas that reach final grade within seven days.
 Seed or sod any areas to remain unworked for more than 30 days.
 Upon completion of project, all disturbed areas must be stabilized and bumps removed if appropriate.

CONSTRUCTION SEQUENCE/NOTES

- IMPLEMENT THE TESC CONSTRUCTION SEQUENCE.
- CLEAR AND GRUB EXISTING VEGETATION AND REMOVE EXISTING CONCRETE PADS.
- EXCAVATE THE INTERIOR OF THE SITE TO DESIGN GRADES LEAVING AN EARTHEN BERM OF EXISTING
- SOIL AS A BARRIER BETWEEN THE EXCAVATION AND THE DUWAMISH RIVER.
 THE EARTHEN BERM WILL A HAVE A MINIMUM TOP WIDTH THAT IS THE GREATER OF 15 FT. OR AS DETERMINED BY THE GEOTECHNICAL ENGINEER. SIDE SLOPE OF THE BERM SHALL BE A MINIMUM OF 2H: 1 V OR AS DETERMINED BY THE GEOTECHNICAL ENGINEER. THE TOP ELEVATION OF THE EARTHEN BERM WILL BE A MINIMUM OF 1 FOOT HIGHER THAN THE EXPECTED HIGH TIDE ELEVATION THROUGH THE DURATION OF CONSTRUCTION.
- WHERE PETROLEUM CONTAMINATED SOILS ARE ENCOUNTERED, OVER EXCAVATE A MINIMUM OF 2 FEET BELOW PETROLEUM TAINTED SOILS AS DIRECTED BY CORPS OR KING COUNTY CONSTRUCTION MANAGER. LIMITS OF CONTAMINATED SOILS WILL BE VERIFIED IN THE FIELD AND/OR WITH LAB TESTING PRIOR TO FINAL GRADING.
- CONTAMINATED SOILS WILL BE STOCKPILED SEPARATELY AND BE TRANSPORTED TO AN APPROVED DISPOSAL SITE IN ACCORDANCE WITH APPLICABLE FEDERAL AND STATE REGULATIONS.
- IN AREAS OF OVER EXCAVATION, BACKFILL WITH CLEAN NATIVE MATERIAL APPROVED BY THE CORPS OR KING COUNTY BIOLOGISTS. BACKFILL MATERIAL SHALL BE SUITABLE FOR PLANTING, BUT NEED NOT BE CLASSIFIED AS TOPSOIL. IF SUITABLE NATIVE SOIL IS NOT AVAILABLE BACKFILL WITH TOPSOIL OR EQUIVALENT MIX AS APPROVED BY KC OR COE BIOLOGIST.
 IN AREAS SHOWN ON THE PLANTING PLAN FOR VEGETATION, UNSUITABLE EXISTING MATERIAL
- WILL BE OVEREXCAVATED BELOW DESIGN GRADE TO A DEPTH AS DIRECTED BY CORPS OR KING COUNTY BIOLOGISTS AND BACKFILLED WITH MATERIAL SUITABLE FOR PLANTING.
- INSTALL LWD PER THE SITE PLAN.
- 10. HYDROSEED ABOVE MHW. PLACE JUTE/COIR FABRIC ON 3:1 SLOPES BELOW MHW
- INSTALL PLANTINGS PER THE PLANTING PLAN.
- REMOVE THE EARTHEN BERM, MAKING THE CONNECTION BETWEEN THE SITE AND THE DUWAMISH RIVER.
- THE EXCAVATION OF THE EARTHEN BERM SHALL BE TIMED WITH TIDAL CYCLE TO MINIMIZE EROSION. THIS MAY REQUIRE THE BERM TO BE REMOVED IN STAGES. IF THE ENTIRE BERM
 CANNOT BE REMOVED WHILE THE TIDE IS OUT, THE EXPOSED OPENING AND SIDE SLOPES WILL BE COVERED WITH PLASTIC SHEETING AND ANCHORED DOWN WITH SAND BAGS TO PREVENT EROSION WHEN THE TIDE COMES BACK
- IF THE EXCAVATION OF THE EARTHEN BERM MUST BE DONE IN STAGES, THEN THE OPENING IN THE EARTHEN BERM MUST BE A MINIMUM OF X FEET WIDE PRIOR TO THE RETURN OF THE HIGHER TIDES (DETERMINED BY HYDRAULICS ENGINEER), OTHERWISE ANOTHER METHOD MUST BE CHOSEN. THIS IS TO PREVENT SIDE CUTTING OF THE SLOPES AND EROSION CAUSED BY HIGHER VELOCITIES OF THE TIDE FLOWING IN AND OUT OF AN OPENING CHANNEL THAT IS TOO SMALL IN SIZE.
- 15. INSTALL ACCESS/VIEWING PATH.
- INSTALL OSPREY POLE.

200

17. INSTALL HAND LAUNCHED BOAT RAMP.

PROJECT DESCRIPTION:

NORTH WIND'S WEIR INTERTIDAL RESTORATION GRADING AND EROSION CONTROL NOTES

ADDRESS LINE 1: DUWAMISH INTERTIDAL NEAR 2724 S. 112TH ST.

CITY, COUNTY, STATE, ZIP CODE TUKWILA, KING, WA, 98186

100

O


SCALE: 1 INCH = 100 FEET


No. 4 Of 8 Sheets


APPLICANT: USACE USACE—Seattle District King County DNRP


REFERENCE No.: PL-04-02 WATERWAY: DUWAMISH RIVER


S.T.R.: SE 1/4 S.4, T.23N, R.4E











PROJECT GOALS AND OBJECTIVES
THE PURPOSE OF THIS PROJECT IS TO RESTORE IMPORTANT INTERTIDAL HABITAT WITHIN THE LOWER DUW AMISH RIVER, WITH THE INTENT OF SPECIFICALLY PROVIDING MUDFLAT AND SALTMARSH HABITATS WILTABLE FOR REARING AND FORAGING BY JUVENILE SALMONIDS. THIS WILL BE ACCOMPLISHED BY REGRADING FILE PROJECT SITE TO INTERTIDAL ELEVATIONS, RECONNECTING THE SITE OTHE RIVER, RESTORING THE NATURAL SHORELINE, AND PLANTING NATIVE INTERTIDAL AND RIPARIAN VEGETATION. THE RESULTING INTERTIDAL MUDFLAT, SALT MARSH, AND RIPARIAN PURPLATIONS WILL PROVIDE CRITICALLY IMPORTANT TRANSITIONAL HABITAT WHERE JUVENILE SALMONIDS WILL HAVE THE OPPORTUNITY TO FEED, REST, AND UNDERGO SMOLTIFICATION PRIOR TO OUT-MIGRATING THROUGH PUGET SOUND TO THE PACIFIC OCEAN. THESE HABITATS WILL ALSO PROVIDE MPORTANT REFUGE, FORAGING, AND PERHAPS BREEDING HABITAT FOR A VARIETY OF OTHER URBAN-ADAPTED NATIVE FISH AND WILLLIES PECIES.

STANDARDS OF SUCCESS
THE PROJECT WILL BE DEEMED SUCCESSFUL IF THE DESIRED INTERTIDAL
HABITATS WITH APPROPRIATE NATIVE PLANT COMMUNITIES ARE CREATED AND
THE SITE DOES NOT EXPERIENCE SIGNIFICANT BANK EROSION. IT IS IMPORTANT
TO NOTE THAT RIVERINE SYSTEMS ARE DYNAMIC AND MINOR ADJUSTMENTS IN
ELEVATIONS AND PLANT COMMUNITIES ARE EXPECTED TO OCCUR OVER TIME.

CONTINGENCY PLAN

IF THE PROJECT FAILS TO MEET THE STATED GOALS AND OBJECTIVES, THE DESIGN TEAM WILL EVALUATE THE CONDITIONS AND IN CONSULTATION WITH PROJECT SPONSORS, LOCAL JURISDICTIONS AND REGULATORY AGENCIES, WILL PREPARE AND IMPLEMENT A CONTINGENCY PLAN TO ADDRESS THE DEFICIENCIES. AS THIS IS A NON-COMPENSATORY, RESTORATION PROJECT, HOWEVER, THE DECISION TO PURSUE FURTHER ACTION THAT IS NOT REQUIRED TO PROTECT EXISTING ENVIRONMENTAL CONDITIONS, ADJACENT ROADWAYS, UTILITIES OR PRIVATE PROPERTY WILL BE AT THE DISCRETION OF THE DESIGN TEAM AND THE PROJECT SPONSORS.

NOTE: TO CONVERT TO SEATTLE AREA TIDE TABLES DATUM, ADD 2.35 FT.

NAVD 88		SEATTLE AREA TIDE TABLES
MHHW	8.97	11.32
MHW	8.12	10.47
MLW	.47	2.82
MLLW	-2.35	0



RIPARIAN/UPLAND PLANTINGS 12-TOP OF SLOPE

TRANSITION: SCRUB/SHRUBS (ELEV. 10-12)



APPLICANT:

INTERTIDAL EMERGENT COMMUNITY (ELEV. 4-10)

MUDFLAT AREA: NO PLANTING PROPOSED (ELEV. -1 TO 4)

WILDLIFE NESTING BOX

USACE-Seattle District

King County DNRP

REFERENCE No.: PL-04-02

WATERWAY: DUWAMISH RIVER

S.T.R.: SE 1/4 S.4, T.23N, R.4E

NORTH WIND'S WEIR INTERTIDAL RESTORATION PLANTING PLAN, DETAIL AND NOTES ADDRESS LINE 1: DUWAMISH INTERTIDAL NEAR 2724 S. 112TH ST.


CITY, COUNTY, STATE, ZIP CODE TUKWILA, KING, WA, 98186

PROJECT DESCRIPTION:

0 100 200

SCALE: 1 INCH = 100 FEET

No. 7 Of 8 Sheets



LEGEND

03-BH-101 BACKHOE TEST PIT YEAR, NUMBER & LOCATION

PROJECT DESCRIPTION:
NORTH WIND'S WEIR INTERTIDAL RESTORATION
SOIL TEST PIT LOCATIONS

ADDRESS LINE 1: DUWAMISH INTERTIDAL NEAR 2724 S. 112TH ST.

CITY, COUNTY, STATE, ZIP CODE TUKWILA, KING, WA, 98186



SCALE: 1 INCH = 100 FEET

No. 8 Of 8 Sheets

APPLICANT:

USACE—Seattle District King County DNRP

REFERENCE No.: PL-04-02

WATERWAY: DUWAMISH RIVER

S.T.R.: SE 1/4 S.4, T.23N, R.4E